

**ADDENDUM #2
TO SPEC. 05-299**

**CREEK STABILIZATION
PROJECT 702211, BEING IN
ANTELOPE CREEK TRIBUTARY FROM
GARFIELD TO VAN DORN STREET**

Addendum #2 to Spec. 05-299 for above project, bids to be opened on Wednesday, December 21, 2005 at 12:00 noon.

Please note the attached changes for the above referenced specification.

All other terms and conditions to remain unchanged.

Dated this 14th day of December, 2005.

Purchasing Department

Vince M. Mejer
Purchasing Agent

ADDENDUM NO. 2**CREEK STABILIZATION PROJECT 702211
ANTELOPE CREEK TRIBUTARY
SPEC. NO. 05-299****TO ALL PROSPECTIVE BIDDERS:**

The quantities and special provisions for the above referenced project are hereby amended to include the following items:

1. Please remove pages 1 through 5 of the Bid Item List and replace with the revised pages 1 through 5.
2. The following changes have been made regarding the Schedule of Quantities/Coordinate Table sheet:

Change the Item Number for 16", 12" & 6" Ductile Iron Pipe Water Main, Cl. 52 to 50.0005.

A revised Schedule of Quantities/Coordinate Table sheet will be supplied to the successful bidder.

All other terms and conditions remain unchanged.

Dated this 14th day of December, 2005.

Purchasing Department,

Vince M. Mejer
Purchasing Agent

Signed Acknowledgement





City of Lincoln

Project Item Schedule

702211

Description: Creek Stabilization Project on Antelope Creek Tributary
between Garfield St. and Van Dorn St.

Location: Antelope Creek Tributary Stabilization Project

Work Type: STORM SEWER

Road Type:

Bid opening Date: 12/14/2005 AT 12:00 pm.

Project Items

Item Number	Quantity	Unit	Unit Price	Extension
Section: 1 Pavement Items				
01.0100	37.400	CY	\$	\$
Pavt & Sidewalk Rem				
08.0025	2,418.000	SF	\$	\$
Modular Block Retaining Wall				
50.0040	228.900	SY	\$	\$
Misc Asphaltic Concrete Pavement, Class 2				
Section 1 Total:				\$
Section: 2 Earthwork Items				
02.0010	1.000	LS	\$	\$
Gen Clearing & Grubbing				
02.0020	7.000	EA	\$	\$
Tree Rem (12" to 23")				
02.0030	7.000	EA	\$	\$
Tree Rem (24" to 35")				
02.0050	7.000	EA	\$	\$
Stump Rem (12" to 23")				

Item Number	Quantity	Unit	Unit Price	Extension
02.0060	7.000	EA	\$	\$
Stump Rem (24" to 35")				
02.0100	17,786.000	CY	\$	\$
Earth Excavation				
Section 2 Total:				\$
Section: 3 Water Items				
23.0690	2.000	EA	\$	\$
Loop Water Service				
23.0690	1.000	EA	\$	\$
Loop Water Service				
23.0690	1.000	EA	\$	\$
Loop Water Service				
23.0920	92.000	LF	\$	\$
Rem 16" Water Main				
23.0930	46.000	LF	\$	\$
Rem 12" Water Main				
23.0950	140.000	LF	\$	\$
Rem 6" Water Main				
50.0005	132.000	LF	\$	\$
Misc 16" DIP Water Main, CI 52				
50.0005	66.000	LF	\$	\$
Misc 12" DIP Water Main, CI 52				
50.0005	160.000	LF	\$	\$
Misc 6" DIP Water Main, CI 52				
Section 3 Total:				\$
Section: 4 Wastewater Items				
50.0005	120.000	LF	\$	\$
Misc Remove Existing 18" Sanitary Sewer Pipe				
Section 4 Total:				\$

Item Number	Quantity	Unit	Unit Price	Extension
Section: 5 Storm Drainage Items				
21.0100	66.000	LF	\$	\$
18" RCP Storm Sewer, CI III				
21.0610	5.000	EA	\$	\$
18" RC FES				
21.0620	1.000	EA	\$	\$
15" RC FES				
21.0940	1.280	CY	\$	\$
Conc for Collars, Elbows & Hdws (In Place)				
21.0950	132.000	LBS	\$	\$
Reinf Steel for Collars, Elbows & Hdws (In Place)				
50.0005	16.000	LF	\$	\$
Misc 8' x 2' Precast Reinforced Concrete Box Storm Sewer				
50.0005	38.000	LF	\$	\$
Misc Remove 18" Storm Sewer Pipe				
50.0010	15.000	CY	\$	\$
Misc Grout Voids, Complete				
50.0015	1.000	LS	\$	\$
Misc Remove & Salvage Existing Ped. Bridge @ Sta. 7+50				
50.0015	1.000	LS	\$	\$
Misc Rem. Ped. Bridge Abutments & Ret. Wall @ Sta. 7+50				
Section 5 Total:				\$
Section: 6 Erosion Control Items				
21.2111	1,514.000	TON	\$	\$
Rip-Rap (In Place)				
30.0090	2.100	AC	\$	\$
Seeding, Ty "D"				

Item Number	Quantity	Unit	Unit Price	Extension
50.0015	1.000	LS	\$	\$
Misc Construction Site Erosion Control				
50.0020	8.800	AC	\$	\$
Misc Seeding, Type 1				
50.0020	1.400	AC	\$	\$
Misc Seeding, Type 2				
50.0020	0.400	AC	\$	\$
Misc Seeding, Type 3				
50.0020	0.500	AC	\$	\$
Misc Seeding, Type 4				
50.0035	1,222.000	TON	\$	\$
Misc Rip-Rap (In Place), Granite or Quartzite				
50.0040	33,733.800	SY	\$	\$
Misc Erosion Control Blanket				
50.0040	20.000	SY	\$	\$
Misc Turf Reinforcement Mat				
Section 6 Total:				\$
Section: 7 Miscellaneous Items				
0.2000	1.000	LS	\$	\$
Const Staking				
0.4000	1.000	LS	\$	\$
Mobilization				
15.0001	1.000	LS	\$	\$
Traffic Ctrl for Const				
50.0005	5,542.000	LF	\$	\$
Misc Construction Fence				
50.0015	1.000	LS	\$	\$
Misc Encase Existing Utility Pipe, Complete				
Section 7 Total:				\$

Item Number	Quantity	Unit	Unit Price	Extension
Estimate Total: \$				

Company Name: _____

Signature: _____ Date: _____