

**ADDENDUM #2
TO SPEC. 06-026**

**WATER MAIN PROJECT 700271
BEING SO. 10TH STREET FROM HIGH TO ARAPAHOE**

Addendum #2 to Spec. 06-026 for above project, bids to be opened on Wednesday, January 18, 2006 at 12:00 noon.

Please note the attached clarification and changes.

All other terms and conditions to remain unchanged.

Dated this 13th day of January, 2006.

Purchasing Department

Vince M. Mejer
Purchasing Agent



ADDENDUM NO. 2

**WATER MAIN PROJECT 700271
S. 10TH ST. FROM HIGH ST. TO ARAPAHOE ST.
SPEC. NO. 06-026**

TO ALL PROSPECTIVE BIDDERS:

The quantities and special provisions for the above referenced project are hereby amended to include the following items:

1. Please remove pages 3 and 4 of the Bid Item List and replace with the revised pages 3 and 4.
2. The following changes have been made regarding the Summary of Quantities sheet:

Remove the following quantity:

<u>Item No.</u>	<u>Description</u>	<u>Unit</u>	<u>Quantity</u>
03.0020	9" P.C. Concrete Pavement	S.Y.	341.5

Add the following quantity:

<u>Item No.</u>	<u>Description</u>	<u>Unit</u>	<u>Quantity</u>
50.0040	9" High Early Strength P.C.C. Pavement	S.Y.	341

A revised Summary of Quantities sheet will be supplied to the successful bidder.

3. The following changes have been made regarding sheet 7 and 8 of the plan set:

Please change the Build Note heading from "9" P.C. Concrete Pavement" to "9" High Early Strength P.C.C. Pavement". All other Build Note items and quantities remain unchanged.

A revised sheet 7 and 8 will be supplied to the successful bidder.

4. Please make the following changes to the "Special Construction Requirements" section of the Special Provisions.

a) Remove item number 3 and replace with the following statement:

"Traffic in S. 10th Street may be reduced to one north bound lane for a maximum of 5 days during the installation of the main and the necessary service line connections. Any restriction requiring more than a two hour period, shall be

counted as a day. Additional lane restrictions needed to complete the work will be permitted during non-peak hours only. (Peak hours: 7:00a – 8:30a, 3:30p – 6:00p). If additional lane restrictions are required to complete the work, during peak hours, they will result in a lane closure fee of \$2,500 per day (or any portion of a day) to be deducted from money due the Contractor. All lane closures or restrictions must be approved in advance by the Engineer.”

5. Please make the following changes to Chapter 3.00 Section 3.14 “High Early Strength P.C. Concrete Pavement” of the Special Provisions.

- a) Remove item A. and replace with the following statement:

“The Contractor shall provide High Early Strength Portland Cement Concrete for use at roadways and drives to facilitate access to adjacent properties or opening of the roadways. High Early Strength Portland Cement Concrete for roadways and drives shall be City of Lincoln L5500 Concrete.”


All other terms and conditions remain unchanged.

Dated this 13th day of January, 2006.

Purchasing Department,

Vince M. Mejer
Purchasing Agent

Signed Acknowledgement



Item Number	Quantity	Unit	Unit Price	Extension
23.0710	130.000	LF	\$	\$
1" Copper Water Service Pipe				
23.0715	110.000	LF	\$	\$
0.75" Copper Water Service Pipe				
23.0735	100.000	LF	\$	\$
Boring For 1" Water Service Pipe				
23.0740	80.000	LF	\$	\$
Boring For 0.75" Water Service Pipe				
23.0950	25.000	LF	\$	\$
Rem 6" Water Main				
50.0001	2.000	EA	\$	\$
Remove Tapping Sleeve and Valve				
23.1150	1.000	EA	\$	\$
Rem Reducer				
			Section 1 Total:	\$
Section: 2 Paving Items				
01.0100	98.500	CY	\$	\$
Pavt & Sidewalk Rem				
01.0130	116.000	SY	\$	\$
5" Conc Base				
01.0151	17.700	TON	\$	\$
AC Surface Course, For Non-Arterial				
01.0210	325.000	LF	\$	\$
Ty "A" Sawing				
01.0220	920.000	LF	\$	\$
Ty "B" Sawing				
06.0020	32.000	LF	\$	\$
Combined Curb & Gutter				

Item Number	Quantity	Unit	Unit Price	Extension
06.0065	800.000	SF	\$	\$
4" Tack-on Conc Median				
50.0040	341.000	SY	\$	\$
Misc 9" High Early Strength P.C.C. Pavement				
Section 2 Total:				\$
Section: 3 Miscellaneous Items				
0.2000	1.000	LS	\$	\$
Const Staking				
0.4000	1.000	LS	\$	\$
Mobilization				
15.0001	1.000	LS	\$	\$
Traffic Ctrl for Const				
Section 3 Total:				\$
Section: 4 Erosion Control Items				
30.0050	0.200	AC	\$	\$
Seeding, Ty "B"				
Section 4 Total:				\$
Estimate Total:				\$

Company Name: _____

Signature: _____ **Date:** _____