

**ADDENDUM #2
TO SPEC. 06-096**

**FACILITY IMPROVEMENT PROJECT 700797
SOUTH STREET MAINTENANCE SHOP**

Addendum #2 to Spec. 06-096 for above project, bids to be opened on Wednesday, March 8, 2006 at 12:00 noon.

Please note the attached clarification and changes.

All other terms and conditions to remain unchanged.

Dated this 1st day of March, 2006.

Purchasing Department

Vince M. Mejer
Purchasing Agent

March 1, 2006

ADDENDUM NO. 2

FACILITY IMPROVEMENT PROJECT 700797
SPEC. NO. 06-096

SOUTH STREET MAINTENANCE SHOP

TO ALL PROSPECTIVE BIDDERS:


The contract documents for the above project are hereby amended as follows:

1. Item No. 0.2000 (Const. Staking) was deleted.
2. Item No. 03.0020 (9" PCC Pavt.) was deleted.
3. Item No. 06.0020 (Combined Curb & Gutter) was deleted.
4. Item No. 03.0060 (9" PCC Pavt. w/int Curb) was added.
5. Item No. 07.0045 (5" Conc. Bikeway) was added.

For further explanation: Manholes and Inlets can be either brick or poured walls, reinforcing steel is not epoxy coated, Traffic Control for Construction is not needed on this project.

Please remove Bid Proposal Sheets and replace with revised Bid Proposal Sheets.

Further, bidders are instructed to attach this Addendum No. 2 to the inside cover of the contract folder as evidence that the Addendum has been received. Failure to do so may result in rejection of the bid.





City of Lincoln

Project Item Schedule

700797

Description: Facility Improvement Project 700797 - South Street
Maintenance Shop

Location: South Street Maintenance Shop

Work Type:

Road Type:

Bid opening Date: 03/08/2006 AT 12:00 pm.

Project Items

Item Number	Quantity	Unit	Unit Price	Extension
Section: 1 Default Section				
0.4000	1.000	LS	\$	\$
Mobilization				
01.0100	451.000	CY	\$	\$
Pavt & Sidewalk Rem				
01.0180	4.000	EA	\$	\$
Adj Water Valve Box To Grade, Cmpl				
01.0220	627.000	LF	\$	\$
Ty "B" Sawing				
02.0010	1.000	LS	\$	\$
Gen Clearing & Grubbing				
08.0010	7,783.000	LBS	\$	\$
Reinf Stl for Steps & Retain Walls (In Place)				
08.0020	96.000	CY	\$	\$
Conc for Steps & Retaining Walls (In Place)				
09.0010	520.000	LF	\$	\$
72" Chain Link Fence (In Place)				

Item Number	Quantity	Unit	Unit Price	Extension
21.0100	871.000	LF	\$	\$
18" RCP Storm Sewer, CI III				
21.0770	3.000	EA	\$	\$
72" Storm Sewer Inlet (Cmpl)				
21.0820	1.000	EA	\$	\$
Grate Inlet, Ty "F-1" (Cmpl)				
21.0850	3.000	EA	\$	\$
Grate Inlet, Ty "H" (Cmpl)				
21.0895	1.000	EA	\$	\$
Storm Sewer MH, 15" - 30" (Cmpl)				
21.1080	1.000	EA	\$	\$
Tap Ex RC Box				
32.0040	500.000	LF	\$	\$
Synthetic Fabric Silt Fence Inst				
32.0050	500.000	LF	\$	\$
Synthetic Fabric Silt Fence Maint				
32.0060	500.000	LF	\$	\$
Synthetic Fabric Silt Fence Rem				
50.0001	1.000	EA	\$	\$
Misc Double Swing Gate				
50.0010	220.000	CY	\$	\$
Misc Topsoil (Black Dirt)				
50.0015	1.000	LS	\$	\$
Misc Oil Water Separator Tank & Piping				
50.0015	1.000	LS	\$	\$
Misc Install & Remove Temporary Trail				
50.0040	847.000	SY	\$	\$
Misc Asphalt Milling Surface, 6" Thick				

Item Number	Quantity	Unit	Unit Price	Extension
50.0045	20,000.000	SF	\$	\$
Misc Seeding, Type 'D'				
03.0060	1,662.000	SY	\$	\$
9" PCC Pavt w/ Int Curb				
07.0045	300.000	SF	\$	\$
5" Conc Bikeway				
Section 1 Total:				\$
Estimate Total:				\$

Company Name: _____

Signature: _____ Date: _____