

**ADDENDUM #1
TO SPEC. 06-144**

**STORM SEWER PROJECT 702194 -
38TH Street & Sewell**

Addendum #1 to Spec. 06-144 for above project, bids to be opened on Wednesday, May 3, 2006 at 12:00 noon.

Please note the attached clarification.

All other terms and conditions to remain unchanged.

Dated this 28th day of April, 2006.

Purchasing Department

Vince M. Mejer
Purchasing Agent

ADDENDUM NO. 1
STORM BOND PROJECT 702194
38TH & SEWELL
SPEC. NO. 06-144



TO ALL PROSPECTIVE BIDDERS:

The quantities and special provisions for the above referenced project are hereby amended to include the following items:

1. The following changes have been made regarding the plans. These changes were made due to the modification of the twin pipes design on High Street into a one pipe design, along with shifting of the proposed manhole at 37th & High St. a few feet north to better facilitate drainage in the area.

The following item quantities have been changed:

<u>Item No.</u>	<u>Description</u>	<u>Old Unit</u>	<u>New Quantity</u>	<u>Quantity</u>
01.0100	Pav't & Sidewalk Removal	C.Y.	1,388	1,379
01.0130	Concrete (5" Base, L5500)	S.Y.	5,007	4,973
01.0151	AC Surface Course for Non Arterial	Ton	804	799
01.0210	Type "A" Sawing	L.F.	11,289	11,281
06.0020	Combined Curb & Gutter	L.F.	1,773	1,752
21.0070	36" R.C.P. Storm Sewer, Class III	L.F.	546	732
21.0095	21" R.C.P. Storm Sewer, Class III	L.F.	859	659
21.0100	18" R.C.P. Storm Sewer, Class III	L.F.	522	337
21.0880	Storm Sewer MH, 42"-48" (Cmpl.)	EA.	2	1
21.0890	Storm Sewer MH, 36" (Cmpl.)	EA.	1	2

Sheets 1, 2, 4, 6, 7, 8, 9, 27 and 37 will be affected by these changes. Revised sheets will be submitted to the successful bidder.

2. Please remove pages 1 through 6 of the Bid Item List and replace with the revised pages 1 through 6.
3. On page 5 of the Contract Agreement, please change the allowable number of calendar days to 151 and the overall completion date to November 1, 2006. The completion date for Phase 1 of this project, specified in the Special Provisions, shall remain the same.

All other terms and conditions remain unchanged.

Dated this 28th day of April, 2006.

Purchasing Department,

Vince M. Mejer
Purchasing Agent

Signed Acknowledgement





City of Lincoln

Project Item Schedule

702194

Description: 38th & Sewell Street Storm Sewer Bond Project- Quantity for Entire Project_Revision 4-26-2006

Location:

Work Type: STORM SEWER

Road Type: RESIDENTIAL

Bid opening Date: 05/03/2006 AT 12:00 pm.

Project Items

Item Number	Quantity	Unit	Unit Price	Extension
Section: 1 Paving Items				
01.0100	1,379.000	CY	\$	\$
Pavt & Sidewalk Rem				
01.0130	4,973.000	SY	\$	\$
01.0150	799.000	TON	\$	\$
AC Surface Course, For Non-Arterial Streets				
01.0160	7.000	TON	\$	\$
Asph Conc for Parking Area				
01.0210	11,281.000	LF	\$	\$
Ty "A" Sawing				
01.0230	902.000	LF	\$	\$
Ty "C" Sawing				
06.0020	1,752.000	LF	\$	\$
Combined Curb & Gutter				
07.0020	3,905.000	SF	\$	\$
4" Conc Sidewalk				

Item Number	Quantity	Unit	Unit Price	Extension
07.0040	987.000	SF	\$	\$
5" Conc Driveway				
07.0100	96.000	SF	\$	\$
Build Detectable Warning Panel				
10.0010	30.000	TON	\$	\$
Crushed Rock Surfacing (In Place)				
Section 1 Total:				\$
Section: 2 Storm Sewer Items				
11.0700	16.000	CY	\$	\$
Flowable Fill				
20.0130	50.000	LF	\$	\$
30" RCP Storm Sewer, BIP				
21.0050	826.000	LF	\$	\$
48" RCP Storm Sewer, CI III				
21.0060	1,323.000	LF	\$	\$
42" RCP Storm Sewer, CI III				
21.0070	732.000	LF	\$	\$
36" RCP Storm Sewer, CI III				
21.0080	374.000	LF	\$	\$
30" RCP Storm Sewer, CI III				
21.0090	495.000	LF	\$	\$
24" RCP Storm Sewer, CI III				
21.0095	659.000	LF	\$	\$
21" RCP Storm Sewer, CI III				
21.0100	337.000	LF	\$	\$
18" RCP Storm Sewer, CI III				
21.0110	1,294.000	LF	\$	\$
15" RCP Storm Sewer, CI III				

Item Number	Quantity	Unit	Unit Price	Extension
21.0770	44.000	EA	\$	\$
72" Storm Sewer Inlet (Cmpl)				
21.0780	9.000	EA	\$	\$
72" Canted Storm Sewer Inlet (Cmpl)				
21.0880	1.000	EA	\$	\$
Storm Sewer MH, 42"-48" (Cmpl)				
21.0885	4.000	EA	\$	\$
Storm Sewer MH, 42" (Cmpl)				
21.0890	2.000	EA	\$	\$
Storm Sewer MH, to 36" (Cmpl)				
21.0895	5.000	EA	\$	\$
Storm Sewer MH, 15" - 30" (Cmpl)				
21.0940	0.800	CY	\$	\$
Conc for Collars, Elbows, Plugs & Hdws (In Place)				
21.1050	1.000	EA	\$	\$
Tap Ex Storm Sewer MH & Replace Invert				
21.1060	3.000	EA	\$	\$
Tap Ex Storm Sewer Inlet & Replace Invert				
21.1070	1.000	EA	\$	\$
Tap Ex RCP				
21.1080	1.000	EA	\$	\$
Tap Ex RC Box				
21.1260	4.000	LF	\$	\$
Rem 42" Storm Sewer Pipe				
21.1290	47.000	LF	\$	\$
Rem 24" Storm Sewer Pipe				
21.1310	91.000	LF	\$	\$
Rem 18" Storm Sewer Pipe				

Item Number	Quantity	Unit	Unit Price	Extension
21.1320	178.000	LF	\$	\$
Rem 15" Storm Sewer Pipe				
21.1710	25.000	EA	\$	\$
Rem Ex Inlet (Cmpl)				
50.0001	1.000	EA	\$	\$
Special Manhole @ Sta. 114+44.40				
50.0001	1.000	EA	\$	\$
Special Manhole @ Sta. 137+64.20				
50.0001	1.000	EA	\$	\$
Special Manhole @ Sta. 139+43.60				
50.0001	1.000	EA	\$	\$
Special Manhole @ Sta. 140+97.50				
50.0005	50.000	LF	\$	\$
15" RCP Storm Sewer, BIP				
Section 2 Total:				\$
Section: 4 Water Main Items				
23.0008	387.000	LF	\$	\$
6" Water Main				
23.0460	2.000	EA	\$	\$
6" Gate Valve, MJ				
23.0490	1.000	EA	\$	\$
Hydrant, Cmpl L=5.5'				
23.0530	110.000	EA	\$	\$
6" Retainer Glands, MJ				
23.0546	25.000	EA	\$	\$
6" X 45 Deg Bend, MJ				
23.0582	1.000	EA	\$	\$
6" X 6" Tee, MJ				

Item Number	Quantity	Unit	Unit Price	Extension
23.0594	1.000	EA	\$	\$
6" Anchoring Coupling, MJ (L=18")				
23.0638	4.000	EA	\$	\$
6" Offset, 24" Drop, MJ				
23.0639	2.000	EA	\$	\$
6" Offset, 18" Drop, MJ				
23.0640	6.000	EA	\$	\$
6" Offset, 12" Drop, MJ				
23.0650	12.000	EA	\$	\$
6" Solid Sleeve, MJ (L=12")				
23.0651	9.000	EA	\$	\$
6" Solid Sleeve, MJ (L=18")				
23.0665	13.780	CY	\$	\$
Conc for Thrust Blocks & Anchorages (In Place)				
23.0670	408.000	LBS	\$	\$
Reinf Stl for Thrust Blks & Anchorages				
23.0685	10.000	EA	\$	\$
Reconstruct Water Service				
23.0690	50.000	EA	\$	\$
Loop Water Service				
23.0715	663.000	LF	\$	\$
0.75" Copper Water Service Pipe				
23.0740	212.000	LF	\$	\$
Boring For 0.75" Water Service Pipe				
23.0950	394.000	LF	\$	\$
Rem 6" Water Main				
23.1100	1.000	EA	\$	\$
Rem Hydrant (Cmpl)				

Item Number	Quantity	Unit	Unit Price	Extension
23.1140	1.000	EA	\$	\$
Rem Gate Valve and Box (Cmpl)				
50.0005	10.000	LF	\$	\$
3" Copper Water Service Pipe				
Section 4 Total:				\$
Section: 5 Sanitary Sewer Items				
22.0820	31.000	EA	\$	\$
Reconstruct Sanitary Sewer Service				
22.0850	860.000	LF	\$	\$
4" Pipe Sewer Service				
50.0010	15.500	CY	\$	\$
(L5500) Conc. Casing for San. Sewer Service Pipe				
Section 5 Total:				\$
Section: 6 Erosion Control Items				
30.0090	0.330	AC	\$	\$
Seeding, Ty "D"				
Section 6 Total:				\$
Section: 7 Miscellaneous Items				
0.2000	1.000	LS	\$	\$
Const Staking				
0.4000	1.000	LS	\$	\$
Mobilization 10% of Total cost				
02.0010	1.000	LS	\$	\$
Gen Clearing & Grubbing				
15.0001	1.000	LS	\$	\$
Traffic Ctrl for Const				
50.0005	20.000	LF	\$	\$
Remove and Replace Retaining Wall				