PROFESSIONAL CIVIL ENGINEER
CRAIG ALDRIDGE
E-11357
09/29/06
STATE OF NEBRASKA

**ADDENDUM NO. 1**

**WATER REPLACEMENT PROJECT 700276**
**SUMNER ST. FROM 27TH ST. TO JEFFERSON AVE.**
**SPEC. NO. 06-281**

**TO ALL PROSPECTIVE BIDDERS:**
Bidders are instructed to attach this Addendum No. 1 to the inside cover of their contract folder and to **sign and fax this page back to Mary Lowe (402-441-6576)** as evidence that the Addendum has been received. Failure to do so may result in rejection of the bid.

Pre-bid conference was held Thursday, September 21, 2006. The following are questions and clarifications from the conference:

Q. Who will be responsible for the removal and replacement of the ornamental street lighting on project 700295, and how will payment of this work be accomplished?

A. **Lincoln Electric System will be responsible for removal and replacement of this pole. The successful contractor will be required to coordinate this work, at least one week prior to construction in this area, with the appropriate LES representative as listed in the Special Provisions. The work involved with removal and replacement of this pole will be billed to the project by LES.**

Clarification: Additional allowances for time associated with water service reconstruction from the stopbox to the house will be allowed on projects.

Clarification: The City of Lincoln will provide a letter of notification to property owners one week prior to start of construction for each location. The Contractor will be responsible for day-to-day notification to property owners for construction activities in the immediate vicinity of their property.

Clarification: The USPS would like prior notification of planned construction activities so that mail service can be accommodated. The contact person with the USPS is:

**Kristi Funcke**
**700 "R" Street**
**Lincoln, NE 68508**
**(402) 473-1642**

The quantities and special provisions for the above referenced project are hereby amended to include the following items:

1. Add the following Special Provision:

## CAPPING OF CONCRETE DURING WINTER CONSTRUCTION

The Contractor will be required to abide by the conditions spelled out in Chapter 1.06 (C) of the 2006 City of Lincoln Standard Specification for Municipal Construction.
If asphalt pavement, to finish the roadway surface, is not available during winter construction, the City of Lincoln will pay the contractor for a concrete pavement cap, at a rate of $90 per C.Y., so that the traveled way can be opened to traffic. Payment to the contractor will be for materials only and the contractor will be responsible for furnishing and paying for the labor, tools, equipment and incidentals necessary for installation, removal and disposal of the concrete cap.

2. Remove the "WATER MAIN SHUTDOWNS" Special Provision and replace with the following:

## WATER MAIN SHUTDOWNS

The following procedure shall be used for shut downs of water mains. These procedures are supplemental to the requirements in the Lincoln Standard Specifications for Municipal Construction.

1. Prior to LWS making the shutdown, the Contractor shall be fully prepared to perform the work in the most expedient manner possible. The Contractor shall have all necessary fittings, pipe, tools, and accessories available onsite to perform the work. If in the opinion of LWS or the Engineer that the contractor is not prepared to perform the work, a shutdown shall not be provided. This condition shall be not cause for claim of damages or additional compensation by the Contractor.

2. If the proposed work involves any fittings to complete the installation, then a plan must be submitted to LWS for approval. The aforementioned plan shall indicate all fittings and dimensions of any pieces to be installed to complete the work causing the shut down. The plan shall indicate the estimated time out of service, requested time for the shutdown, general description of how the work will be performed, required pumping equipment and the number of employees expected to perform the work

3. The water main shall be excavated prior to the shutdown and the excavation prepared to make work conditions safe and clean. Where directed by LWS or the Engineer, the contractor shall use crushed rock or crushed concrete in the bottom of the excavation to provide a suitable

work surface for ease of construction and to provide for sanitary conditions. These materials shall be compensated in accordance to applicable bid items.

4. Contractors shall be adequately equipped to pump drain water and anticipate some leakage of water past valves. Adequate pumping equipment shall be shall be a condition for approval of the shut down plan.

5. All parts/pieces necessary to complete the work must be preassembled to the extent possible prior to the actual valve closure or the water will not be shut off.

6. There shall be no cost for a shut down which interrupts water service for less than two (2) hours. For interruptions of water service lasting two (2) or more hours the Contractor shall be charged $100 for each hour or portion of an hour past the initial two (2) period of time. The shut down time shall be considered the time from when the water main has been isolated by the Lincoln Water System (LWS) to the extent the possible up to the time that LWS is notified that work has been completed sufficiently to allow service to be restored.

All other terms and conditions remain unchanged.

Dated this 29th day of September, 2006.

PROFESSIONAL CIVIL ENGINEER
CRAIG
E-11357
09/29/06
STATE OF NEBRASKA