

5.1 27th Street and O Street

BEFORE

ADT: 66,200 veh/day (2002)


Time Period:

2003

Traffic Control: Actuated Coordinated Signal

Crash Pattern:

EB Left Turns



Total Crashes in Before Period: 40



27th Street & O Street - Westbound Approach (Before)

5.1 27th Street and O Street

AFTER

Countermeasures: Constructed EB & WB Dual Left Turn Lanes, Rebuilt Traffic Signal, Removed Eastbound Right Turn Lane


Time Period:

2005

Improvement Completion Date: Summer 2004

Speed Limits:

NS Arterial- 35 mph
EW Arterial- 35 mph



Total Crashes in After Period: 66



27th Street & O Street - Westbound Approach (After)

5.1 27th Street and O Street

COMPARISON

Countermeasures:

Constructed EB & WB Dual Left Turn Lanes, Rebuilt Traffic Signal, Removed Eastbound Right Turn Lane

Improvement Completion Date:

Summer 2004

	Before	After	Change
Analysis Period	2003	2005	-
Primary Crash Benefit			
Total Number of Correctable Crashes	26	32	23%
All Other Intersection Crashes	14	34	143%
Intersection Crash Experience			
Injury + Fatal Crashes	13	12	-8%
Property Damage-Only Crashes	23	35	52%
Non-Reportable Crashes	4	19	375%
<i>Total Number of Intersection Crashes</i>	<i>40</i>	<i>66</i>	<i>65%</i>
Total Intersection Benefit			
Crash Rate	1.66	2.73	64%
EPDO Rate	6.06	6.62	9%
EPDO Number*	146.48	159.99	13.51

Cost of Property Damage Crash: \$ 8,200
 Total Benefit (12 months): \$ (110,782)
 Equivalent Uniform Annual Benefit (EUAB): \$ (142,206)

Total Cost of Improvements:

Equivalent Uniform Annual Cost (EUAC): \$ 38,875
 Initial Cost: \$ 445,895

Benefit-Cost Ratio:
$$\frac{\$ (142,206)}{\$ 38,875} = -3.7$$

Net Benefit (Present Worth): \$ (142,206) - \$38,875 = (\$181,081)

**Change NOT Statistically Significant at 95% Confidence Interval*

This page intentionally left blank.