



Oak Creek Basin Trunk Sewer
And Sub-Basin Sewers

**Preliminary Design
Report**

Lincoln Wastewater System
Lincoln, Nebraska

May 2006

City Project No. 502 940

Specification No. 04-312

HDR Project 20843

Oak Creek Preliminary Design Report	Page Number
Executive Summary	
1. Introduction	ES-1
2. Findings and Evaluations of Investigations in the Project Area	ES-2
3. Summary of Trunk Sewer Evaluation and Alignment Studies	ES-2
4. Improvement Plan for 5,950 Acres (1,500 Tier III Acres)	ES-4
5. Improvement Plan for 4,450 Acres (Existing and Tier I Areas)	ES-5
6. Project Costs for Selected Improvements	ES-6
7. Additional Study of Sewer Alternative along W. Mathis Street (Segment E-2)	ES-7
8. Conclusions and Recommendations	ES-7
1. Introduction	1-1
1.1. Scope of Study	1-1
1.2. Background	1-1
1.3. Previous Studies	1-2
1.3.1. Lincoln Wastewater Facilities Plan Update	1-2
1.3.2. Airpark West Subarea Plan	1-3
1.3.3. Northwest Tier Study	1-5
1.4. Other Documents	1-5
1.5. Study Area	1-6
1.6. Stakeholders	1-6
2. Findings and Evaluation of Investigations in the Project Area	2-1
2.1. Geotechnical Investigations	2-1
2.2. Concrete Rubble Pit	2-2
2.3. Surveying	2-2
2.4. Condition Assessment of Existing Wastewater Facilities	2-2
2.5. Existing Utilities	2-3
2.5.1. Alltel	2-4
2.5.2. Aquila	2-4
2.5.3. Lincoln Electric System	2-5
2.5.4. Lincoln Water System	2-6
2.5.5. Watershed Management	2-6
2.5.6. Magellan Pipeline Company	2-6
2.5.7. Sprint	2-6
2.5.8. Lincoln Airport Authority Utilities	2-7
2.6. Environmental	2-7
2.6.1. Wetlands	2-7
2.6.2. Hazardous Substances	2-7
2.7. Pavement and Traffic Impacts	2-8
2.8. Proposed Roadway Improvements	2-8
2.9. Proposed Natural Resources District Improvements	2-9
2.10. Public Relations	2-9
2.11. Impacts and Disruptions to Existing Businesses	2-9
2.12. Easements and Land Acquisition	2-10
2.13. Permits and Approvals	2-10

Oak Creek Preliminary Design Report	Page Number
3. Summary of Alignment Studies and Trunk Sewer Evaluation	3-1
3.1 Trunk Sewer Evaluation	3-1
3.2 Summary of Alignment Studies	3-3
3.2 Order of Magnitude OPPC	3-5
4. Improvement Plan for 5,590 Acres (1,500 Tier III Acres)	4-1
4.1. Applicable Standards and Guidelines	4-1
4.2. Sewer Services Areas (Development Areas)	4-1
4.3. Design Flows and Sewer Modeling (Existing, Tier I, Future)	4-2
4.4. Sewer Replacement Evaluation	4-3
4.5. Siphon Design	4-5
4.6. Connections to Existing and Future Sewers	4-6
4.7. Pipe Design	4-6
4.8. Manholes	4-7
4.9. Construction Techniques	4-7
4.10. Special Construction	4-8
4.11. Abandoning of Existing Sewers	4-8
4.12. Project Approval Requirements	4-9
5. Improvement Plan for 4,450 Acres (Existing and Tier I Areas)	5-1
5.1. Applicable Standards and Guidelines	5-1
5.2. Sewer Services Areas (Development Areas)	5-1
5.3. Design Flows and Sewer Modeling (Existing, Tier I, Future)	5-2
5.4. Sewer Replacement Evaluation	5-3
5.5. Siphon Design	5-5
5.6. Connections to Existing and Future Sewers	5-6
5.7. Pipe Design	5-6
5.8. Manholes	5-7
5.9. Construction Techniques	5-7
5.10. Special Construction	5-8
5.11. Abandoning of Existing Sewers	5-8
5.12. Project Approval Requirements	5-9
6. Project Costs for Selected Improvement	6-1
6.1. Basis of Project Costs	6-1
6.2. Construction and Engineering Costs	6-1
6.3. Easement Acquisition Costs	6-1
6.4. Total Project Costs	6-2
7. Additional Study of Sewer Alternative Along West Mathis Street	7-1
7.1. Utility Conflicts	7-1
7.2. Modeling of Existing Trunk Sewer from MH 68 to the Oak Creek Siphon	7-2
7.3. Proposed Improvements of the Existing Trunk Sewer	7-3
7.4. Project Costs	7-4

Oak Creek Preliminary Design Report	Page Number
7.5. Phased Development Plan Summary	7-5
7.6. Present Value Cost	7-5
7.7. Comparison to Recommended Development Plan in Study	7-6
7.8. Phased Development of the Preliminary Design Study	7-6
8. Conclusions and Recommendations	8-1
8.1. Conclusions	8-1
8.2. Summary of Additional Study in Appendix G	8-1
8.3. Summary of Additional Study in Appendix H	8-2
8.4. Project Costs	8-2
8.5. Recommended Phased Development Plan	8-3
8.6. Phase 1 Project	8-4
8.7. 1,500 Acres of Tier III Development	8-5
Tables:	Page Number
ES-1 Oak Creek Basin Areas	ES-4
ES-2 Phased Const. of the Proposed Collection System Improvements (5,950 ac)	ES-4
ES-3 Oak Creek Basin Areas	ES-5
ES-4 Phased Const. of the Proposed Collection System Improvements (4,450 ac)	ES-4
ES-5 Opinion of Probable Project Costs (5,950 acres of Development in Basin)	ES-6
ES-6 Opinion of Probable Project Costs (4,450 acres of Development in Basin)	ES-6
ES-7 Opinion of Probable Project Costs (5,950 acres of Development in Basin)	ES-8
ES-8 Opinion of Probable Project Costs (4,450 acres of Development in Basin)	ES-8
ES-9 Phased Const. of the Proposed Collection System Improvements	ES-9
2-1 Utility Contact Information	2-3
2-2 Permit Information and Contact List	2-10
3-1 Hydraulic Model Inputs for Existing Oak Creek Basin	3-1
3-2 Facility Plan Update Identified Trunk Sewer Improvements	3-2
3-3 Additional Service Area Capacity at Manhole 68	3-2
3-4 Summary of Existing Capacity in the Oak Creek Collection System	3-5
4-1 Oak Creek Basin Areas	4-1
4-2 City of Lincoln Sewer Design Flow Parameters	4-2
4-3 Hydraulic Model Inputs for Existing Oak Creek Basin	4-2
4-4 Hydraulic Model Inputs for Proposed Future Flows	4-3
4-5 Phased Construction of the Proposed Collection System Improvements	4-5
4-6 Individual Siphon Design for Each Flow Condition	4-5
4-7 Composite Siphon Design for All Flow Conditions	4-5
5-1 Oak Creek Basin Areas	5-1
5-2 City of Lincoln Sewer Design Flow Parameters	5-2
5-3 Hydraulic Model Inputs for Existing Oak Creek Basin	5-2
5-4 Hydraulic Model Inputs for Proposed System Flows	5-3

Tables:		Page Number
5-5	Phased Construction of the Proposed Collection System Improvements	5-5
6-1	Opinion of Probable Project Costs (5,950 acres of Development in Basin)	6-2
6-2	Opinion of Probable Project Costs (4,450 acres of Development in Basin)	6-2
7-1	Hydraulic Conveyance Limitations in the Existing Segment E-2	7-2
7-2	Opinion of Probable Project Costs	7-4
7-3	Phased Construction of the Alternative Development Plan for Segment E-2	7-5
7-4	Present Value Costs	7-5
7-5	Phased Development Costs for the Preliminary Design Study	7-6
8-1	Opinion of Probable Project Costs (5,950 acres of Development in Basin)	8-3
8-2	Opinion of Probable Project Costs (4,450 acres of Development in Basin)	8-3
8-3	Phased Construction of the Proposed Collection System Improvements	8-4

Figures:		Following Page
1-1	Basin Area Map	1-1
1-2	Airport West Subarea Plan	1-3
1-3	Airpark West Master Plan	1-3
2-1	Critical Locations, Excavations, Boring Locations, Other Investigation Information (Utilities)	2-1
3-1	Existing Oak Creek Trunk Sewer (MH 68 to Theresa Street WWTF)	3-1
3-2	Trunk Sewer – MH 68 to Theresa Street WWTF (Tier I Flows)	3-2
3-3	Trunk Sewer – MH 68 to Theresa Street WWTF (Tier I + Future 1,500 Acres)	3-2
4-1	Existing Collection System	4-1
4-2	Existing Sewer Capacities	4-2
4-3	Proposed Sewer Location Map	4-3
4-4	Proposed East Basin Sewer to Manhole 68 (Tier I + Future 1,500 Acres)	4-3
4-5	Proposed West Basin Sewer to Manhole 68 (Tier I + Future 1,500 Acres)	4-3
4-6	Proposed Oak Creek Siphon (Tier I + Future 1,500 Acres)	4-3
4-7	Segment 6c and 6d – Existing 15” Sewer (Tier I Flows)	4-4
4-8	Segment 6c and 6d – Proposed 18” Sewer (Tier I Flows)	4-4
4-9	Oak Creek Siphon Design	4-5
7-1	Additional Study Alternatives A & B	7-1
7-2	Additional Study Alternative A	7-1
7-3	Existing Sewer from Manhole AA6-68 to Manhole AA7-26	7-2
7-4	Phase 1 Improvements from Manhole AA6-68 to Manhole AA7-26	7-2
7-5	Phase 2 Improvements from Manhole AA6-68 to Manhole AA7-26	7-3
7-6	Phase 3 Improvements from Manhole AA6-68 to Manhole AA7-26	7-3

Appendix:

- A. Preliminary Plan and Profile Drawings (200' scale)
- B. Opinion of Probable Project Cost
- C. Alignment Studies
- D. Preliminary Geotechnical Report
- E. SWMM Model Input Nodes and Segments (Existing and Proposed Collection System)
- F. Design Basin Growth Curves for Sewer Parallel and Replacement
- G. Capacity Analysis of Segment E-2
- H. Analysis of Varying Design Flows, 'n' Factors, and In-Basin Pumping to Reduce Project Costs