

Table 2-4 Results of Public Access Street Flooding

Management Alternative	Total Length (ft)	Estimated Cost	Percent Reduction
No Net Rise/Compensatory Storage	69,863	\$1,981,000	27%
0.5-ft Rise in Existing 100-Yr WSE	70,747	\$2,320,000	14%
1.0-ft Rise in Existing 100-Yr WSE (Existing City Policy)	75,524	\$2,707,000	Base