


Alignment Study Report



Final Copy

BEAL SLOUGH RELIEF TRUNK SEWER PHASES I & II



prepared for

Lincoln Wastewater System Lincoln, Nebraska

PN 134056.0201



October 2003



Beal Slough Relief Trunk Sewer Alignment Study Report

Table of Contents

Table of Contents

	<u>Page</u>
Executive Summary	
1. Introduction	ES-1
2. Description of Proposed Alignment Alternatives	ES-1
3. Findings and Evaluation of Alignment Selection Factors	ES-3
4. Project Costs for Alternatives	ES-4
5. Conclusions and Recommendations	ES-4
6. Replacement Sewer	ES-5
1.0 Introduction	
1.1 Scope of Study	1-1
1.2 Background	1-1
1.3 Study Area	1-2
2.0 Description of Proposed Alignment Alternatives	
2.1 Alignment No. 1	2-1
2.2 Alignment No. 2	2-2
2.3 Alignment No. 3	2-2
3.0 Findings and Evaluation of Alignment Selection Factors	
3.1. Length of Sewer	3-1
3.2. Length of Tunnel Crossings	3-2
3.3. Geotechnical	3-4
3.4. Existing Utilities	3-5
3.4.1. Lincoln Water System	3-5
3.4.2. Storm Sewers	3-6
3.4.3. Lincoln Electric System	3-7
3.4.4. Alltel	3-9
3.4.5. MCI	3-9
3.4.6. Qwest	3-9
3.4.7. Aquila	3-9
3.5. Railroad Impacts	3-10

Beal Slough Relief Trunk Sewer Alignment Study Report

Table of Contents

	<u>Page</u>
3.6. Pavement and Traffic Impacts	3-11
3.7. Proposed Road Improvements	3-12
3.8. Proposed Stormwater Improvements	3-13
3.9. Connections with Existing Sewers	3-14
3.10. Public Relations	3-16
3.11. Impacts and Disruptions to Existing Businesses	3-17
3.12. Environmental	3-18
3.12.1. Wetlands	3-18
3.12.2. Hazardous Substances	3-19
3.12.3. Cultural Resources	3-20
3.13. Construction Techniques	3-20
3.14. Hydraulic Design	3-21
3.15. Constructibility Requirements	3-22
3.16. Construction Impacts on Existing Sewer	3-23
3.17. Potential Risks During Construction	3-23
3.18. Easement and Land Acquisition	3-24
3.19. Permits and Approvals	3-25
3.20. Summary of Alignment Selection Factors	3-26
4.0 Project Costs for Alternatives	
4.1. Basis of Project Costs	4-1
4.2. Construction and Engineering Costs	4-1
4.3. Easement Acquisition Costs	4-1
4.4. Total Project Costs	4-2
5.0 Conclusions and Recommendations	
5.1. Conclusions	5-1
5.1.1. Project Costs	5-1
5.1.2. Ranking Factors Results	5-1
5.2. Recommended Alternative	5-2

Beal Slough Relief Trunk Sewer Alignment Study Report

Table of Contents

	<u>Page</u>
6.0 Replacement Sewer	
6.1. Options for Replacement of Existing Sewer	6-1
6.1.1. Insituform	6-1
6.1.2. Replacement Sewer	6-2
6.2. Conclusion	6-2

TABLES

3-1	Length of Sewer for Each Alignment	3-2
3-2	List of Tunnels and Length for Alignments	3-3
3-3	Wastewater Model Flow Input Locations	3-22
3-4	Summary of Route Alignment Selection Factors	3-27
4-1	Preliminary Opinions of Probable Costs	4-2

Following Page

FIGURES

1-1	Existing Beal Slough and Salt Valley Trunk Sewers	1-1
1-2	Beal Slough Drainage Basin	1-2
2-1	Beal Slough Alignments (SVTRTS to 14 th Street)	2-3
2-2	Beal Slough Alignments (14 th Street to 27 th Street)	2-3
2-3	Beal Slough Alignments (27 th Street to 36 th Street)	2-3
2-4	Beal Slough Alignments (36 th Street to 47 th Street)	2-3
2-5	Beal Slough Alignments (47 th Street to 56 th Street)	2-3

APPENDICES

A	Opinion of Probable Project Costs for Alignments
B	EDR Area Study Report Memorandum
C	Opinion of Probable Project Costs for Replacement Sewer