Lincoln Wastewater Facilities Plan

UPDATE

April 2003

BROWN AND CALDWELL

MWH
MONTGOMERY WATSON HARZA

CONTENTS

TABLES vi

FIGURES viii

CHAPTER 1. EXECUTIVE SUMMARY 1-1
Background 1-1
Planning Goals and Objectives 1-1
Study Area Boundaries 1-1
Population Projections 1-2
Wastewater Collection 1-2
Collection System Needs 1-3
Wastewater Treatment 1-6
Wastewater Flows 1-6
Existing Treatment Facilities 1-6
Treatment Requirements 1-7
Existing Treatment Capacities 1-7
Preferred Treatment Alternatives 1-8
Improvement Costs 1-11

CHAPTER 2. INTRODUCTION 2-1
Background 2-1
Factors Affecting the Facilities Planning Study 2-1
Regulatory Changes 2-1
Population Increase 2-2
Aging Facilities 2-2
Planning Goals and Objectives 2-3

CHAPTER 3. PLANNING AREA CHARACTERISTICS 3-1
Study Area Boundaries 3-1
Physical Characteristics 3-3
100-Year Flood Plain Areas 3-6
Planning Agencies 3-6
Existing Land Usage 3-6
Population Growth 3-7
Historical Populations 3-7
Population Projections 3-8
Collection System Land-Use Plan 3-10

CHAPTER 4. EVALUATION OF EXISTING WASTEWATER FACILITIES 4-1
Description of Existing Collection System 4-1
Salt Creek 4-1
West "O" Street 4-1
Beals Slough 4-3

Haines Branch 4-3
Middle Creek 4-3
Antelope Creek 4-3
East Campus 4-3
Oak Creek 4-3
Little Salt Creek 4-3
Lynn Creek 4-3
Deadmans Run 4-4
Havelock 4-4
Regent Heights 4-4
Collection System Needs 4-4
Description of Existing Wastewater Treatment Facilities 4-4
Theresa Street Wastewater Treatment Facility 4-4
Northeast Wastewater Treatment Facility 4-10
Existing Treatment Capacity Analysis 4-13
Factors Affecting Treatment Capacity 4-13
Capacity Estimate Methodologies 4-23
Theresa Street WWTF Capacity Estimate 4-23
Northeast WWTF Capacity Estimate 4-26
Improving Capacity Estimates 4-27
Hydraulic Capacity Analysis 4-27
Hydraulic Profile Modeling 4-27
Theresa Street WWTF 4-28
Northeast WWTF 4-29
Lincoln Wastewater Residuals Management 4-30
Screenings and Grit 4-30
Primary and Secondary Sludges 4-30
Theresa Street WWTF Digested Sludge Handling and Disposal 4-31
Northeast WWTF Digested Sludge Handling and Disposal 4-33
Identification of Needs 4-35
Theresa Street WWTF 4-35
Northeast WWTF 4-36
Treatment Facility Capacity Summary 4-37

CHAPTER 5. WASTEWATER FLOW AND LOAD PROJECTIONS 5-1
Terminology 5-1
Average Daily Flow (ADF) 5-1
Maximum Monthly Flow (MMF) 5-1
Peak Daily Flow (PDF) 5-1
Peak Hourly Flow (PHF) 5-1
Infiltration and Inflow (I/I) 5-1
Peak Wet Weather Flow (PWWF) 5-2
Existing/Historical Flows 5-2
Wet Weather Flows 5-3

Historical Wastewater Composition 5-5
Theresa Street WWTF Influent Wastewater Composition 5-5
Northeast WWTF Influent Wastewater Composition 5-9
Projected Waste Flows and Loads 5-14
Projected Flow Rates 5-14
Projected Peak Wet Weather Flows 5-17
Projected Wastewater Loadings 5-18
Projected Wastewater Solids Production Rates 5-21
Summary 5-23

CHAPTER 6. REGULATORY REQUIREMENTS 6-1
Current Water Quality Standards 6-1
State Stream Use Classifications 6-1
Salt Creek Classification 6-2
Nebraska Discharge Permitting System 6-2
Current Theresa Street WWTF NPDES Permit 6-3
Current Northeast WWTF NPDES Permit 6-4
Potential Future NPDES Permits 6-5
Potential Ammonia Effluent Limits 6-5
Current Wastewater Residuals Disposal Regulations 6-7
Screenings and Grit 6-8
Primary and Secondary Sludges 6-8
Reporting Requirements 6-11
Clean Water Act 6-12
RCRA Hazardous Waste Regulations, 40 CFR Part 261 6-12
Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) 6-13
Evolving Regulations and Standards 6-13
Clean Water Act Reauthorization 6-13
Clean Water Action Plan 6-13
National Criteria Revisions - Water Quality Criteria and Standards Plan 6-14
TMDL Regulation 6-15
Nutrient Criteria 6-16
Bacteria Standards 6-17
Whole Effluent Toxicity 6-17
Sanitary Sewer Overflows (SSO) 6-18
Sediment Criteria 6-18
Stormwater Discharge Regulation 6-18
Clean Air Act Amendments (CAAA) 6-18

CHAPTER 7. BASIS OF PROJECT DEVELOPMENT 7-1
2002 Lincoln-Lancaster County Comprehensive Planning 7-1
Design Period and Project Staging 7-1

Economic Evaluation 7-1
Present Worth Analysis 7-1
Assigning Costs 7-2
Capital Costs 7-2
Collection System 7-3
Treatment Facilities 7-3
Site Work 7-4
Foundations 7-4
Yard Piping 7-4
Electrical and Instrumentation 7-4
Treatment Facilities 7-4
Land 7-4
Collection Facilities 7-4

CHAPTER 8. DEVELOPMENT AND EVALUATION OF ALTERNATIVES 8-1
Anticipated Collection System Needs 8-2
Salt Creek 8-3
West "O" Street 8-7
Beals Slough 8-8
Haines Branch 8-8
Middle Creek 8-9
Antelope Creek 8-9
East Campus 8-10
Oak Creek 8-10
Little Salt Creek 8-11
Lynn Creek 8-11
Deadmans Run 8-12
Havelock 8-13
West Stevens Creek 8-13
Summary of Collection System Needs 8-14
Theresa Street WWTF 8-14
Description of Alternatives 8-14
Common Alternative Components 8-18
Key Treatment Issues 8-19
Theresa Street Alternative 1 - Pretreatment of Cook Foods Wastewater 8-19
Theresa Street Alternative 2 - Treat Side-Streams from Solids Processing 8-21
Theresa Street Alternative 3 - Pretreat Cook Foods and Ammonia Side-Stream Treatment 8-23
Theresa Street Alternative 4 - Expand Activated Sludge System 8-24
Summary of Theresa Street WWTF Alternatives 8-26
Theresa Street WWTF Basic Improvements 8-28
Northeast WWTF 8-29
Northeast WWTF Basic Improvements 8-31

CHAPTER 9. PREFERRED WASTEWATER MANAGEMENT SYSTEM 9-1
Preferred System Description 9-1
Collection System Improvements 9-1
Theresa Street WWTF Improvements 9-4
Northeast WWTF Improvements 9-4
Wet Weather Flows 9-4
General Considerations 9-4
Preferred Treatment System Costs 9-8
Implementation of Preferred System 9-8
Collection System 9-13
Theresa Street WWTF 9-13
Northeast WWTF 9-14
Anticipated Capital Expenditures 9-15

GLOSSARY

APPENDICES

TABLES

No.		Page
1-1	City/County Population Projections	1-2
1-2	Wastewater Flow Projections	1-6
1-3	Anticipated Effluent Ammonia Limits	1-7
1-4	Capacity Summary - Lincoln Wastewater Treatment Facilities	1-8
1-5	Tier I Improvement Costs	1-11
3-1	Historical City/County Population Growth	3-8
3-2	City/County Population Projections	3-10
4-1	Primary Factors Affecting Treatment Capacity of an Activated Sludge System	4-14
4-2	Anticipated Effluent Ammonia Limits	4-15
4-3	Summary of Historical Peak Flow Factors	4-20
4-4	Nitrification Capacity Summary - Existing Theresa Street WWTF	4-26
4-5	Nitrification Capacity Summary - Existing Northeast WWTF	4-26
4-6	Theresa Street WWTF Anaerobic Digester Size and Loading Summary	4-31
4-7	Theresa Street Sludge Dewatering Facility Summary	4-31
4-8	Theresa Street Biosolids Pollutant Concentration Data	4-32
4-9	Northeast WWTF Anaerobic Digester Capacity Summary	4-33
4-10	Northeast WWTF Land Application Facilities	4-34
4-11	Northeast Biosolids Pollutant Concentration Data	4-35
4-12	Nitrification Capacity Summary – Existing Lincoln Wastewater Treatment Facilities	4-37
5-1	Historical Wastewater Flows	5-2
5-2	Design Dry Weather Flow Values	5-3
5-3	1995-2001 Theresa Street WWTF Influent Characteristics	5-9
5-4	1995-2001 Northeast WWTF Influent Characteristics	5-9
5-5	Wastewater Flow Projections	5-14
5-6	Peak Wet Weather Flow Components	5-17
5-7	Peak Wet Weather Design Flows	5-17
5-8	WWTF Loading Rate Projections	5-18
5-9	Projected Solids Production Rates	5-21
5-10	Summary of Projected Flows and Loads	5-23
6-1	NPDES Permit Limitations - Theresa Street WWTF	6-3
6-2	NPDES Permit Monitoring Requirements - Theresa Street WWTF	6-4
6-3	NPDES Permit Limitations - Northeast WWTF	6-5
6-4	NPDES Permit Monitoring Requirements - Northeast WWTF	6-5
6-5	Anticipated Effluent Ammonia Limits	6-6
6-6	Summary of 503 Regulations Applicable to Land Application of Biosolids	6-9
6-7	Summary of Class A Biosolids Criteria	6-10
6-8	Summary of Class B Biosolids Criteria	6-10
6-9	US EPA Proposed Nutrient Criteria for Ecoregion VI	6-17
7-1	Construction Cost Estimation	7-2

8-1 Summary of Recommendations For Existing Collection System..... 8-15
8-2 Lincoln Future Wastewater Collection System Served Acreages (25 year - Tier I)..... 8-16
8-3 Lincoln Future Wastewater Collection System Service Acreages (50 year - Tier II) 8-17
8-4 Treatment Capacity Scenarios to Meet Year 2025 and Projected Wastewater Flows at the Theresa Street WWTF 8-18
8-5 Theresa Street Alternative 1 - Year 2025 Required Improvements..... 8-21
8-6 Theresa Street Alternative 2 - Year 2025 Required Improvements..... 8-23
8-7 Theresa Street Alternative 3 - Year 2025 Required Improvements..... 8-24
8-8 Theresa Street Alternative 4 - Year 2025 Required Improvements..... 8-26
8-9 Alternative Capital Cost Summary..... 8-26
8-10 Northeast WWTF Phase I Expansion Cost..... 8-30
9-1 Summary of Recommended Trunk Sewer Improvements to Serve Tier I Needs (A & B Priority) 9-2
9-2 Summary of Recommended Collection System Improvements to Serve Tier II Needs 9-3
9-3 Theresa Street WWTF Estimated Capital Improvement Costs 9-12
9-4 Northeast WWTF Estimated Capital Improvement Costs..... 9-13
9-5 Tier I Improvement Costs 9-15

FIGURES

No.		Page
1-1	Existing Wastewater Collection System	1-4
1-2	Recommended Tier I Wastewater Collection System Improvements	1-5
1-3	Proposed Site Layout For Theresa Street WWTF	1-9
1-4	Proposed Site Layout For Northeast WWTF	1-10
1-5	Capital Improvement Costs Through the Tier I Planning Period	1-12
3-1	Study Area	3-2
3-2	Drainage Basins	3-4
3-3	Tier I Priority A and B Needs	3-5
3-4	Historical and Projected Populations for the City of Lincoln and Lancaster County	3-9
3-5	Projected Service Area	3-11
4-1	Existing Lincoln Wastewater Collection System	4-2
4-2	Facility Location Map	4-5
4-3	Theresa Street WWTF Process Schematic	4-8
4-4	Theresa Street WWTF Solids Handling Schematic	4-9
4-5	Northeast WWTF Process Schematic	4-11
4-6	Northeast WWTF Solids Handling Schematic	4-12
4-7	Effect of Aerobic SRT on Effluent Ammonia	4-16
4-8	Monthly Average Influent Wastewater Temperatures Theresa Street WWTF	4-17
4-9	Daily and 30-day Average Primary Effluent COD Theresa Street WWTF	4-19
4-10	Theresa Street WWTF Monthly Average Flows	4-21
4-11	Northeast WWTF Monthly Average Flows	4-22
4-12	West Side Capacity vs. MLSS Concentration	4-24
4-13	East Side Capacity vs. MLSS Concentration	4-25
5-1	Average Annual Wastewater Flow	5-4
5-2	Monthly Average Influent BOD & COD Concentrations Theresa Street WWTF	5-6
5-3	Historical BOD_5 Monthly Average Loading Theresa Street WWTF	5-7
5-4	Historical TSS Monthly Average Loading Theresa Street WWTF	5-8
5-5	Historical Monthly Average Influent BOD & COD Concentrations Northeast WWTF	5-10
5-6	Historical Monthly Average Influent TSS Concentrations Northeast WWTF	5-11
5-7	Historical Monthly Average BOD_5 Loading Northeast WWTF	5-12
5-8	Monthly Average TSS Loadings Northeast WWTF	5-13
5-9	Average Annual Flow and Flow per Capita	5-15
5-10	Projected Annual Average Wastewater Flows	5-16
5-11	Average Yearly BOD_5 Loading per Capita Theresa Street WWTF	5-19
5-12	Average Yearly TSS Loading per Capita Theresa Street WWTF	5-20

5-13 Digester Feed Sludge Projections (2000-2050) Theresa Street WWTF 5-23
8-1 Tier I Development 8-4
8-2 Tier II Development 8-5
8-3 Alternative 1 - Conceptual Site Plan 8-20
8-4 Alternative 2 - Conceptual Site Plan 8-22
8-5 Alternative 3 - Conceptual Site Plan 8-25
8-6 Alternative 4 - Conceptual Site Plan 8-27
8-7 Northeast WWTF Conceptual Site Plan 8-33
9-1 Recommended Tier I Collection System Improvements 9-5
9-2 Recommended Conceptual Theresa Street Site Plan 9-6
9-3 Recommended Conceptual Northeast Site Plan 9-7
9-4 Theresa Street WWTF Conceptual Site Plan - Future 9-9
9-5 Northeast WWTF Conceptual Site Plan - Future 9-10
9-6 Lincoln Capital Improvement Schedule 9-11
9-7 Lincoln WW Collection System Projected Capital Expenditures 9-16
9-8 Theresa Street WWTF Projected Capital Expenditures 9-17
9-9 Northeast WWTF Projected Capital Expenditures 9-18
9-10 Total Lincoln Wastewater Projected Capital Expenditures 9-19